



REPLY TO BIDDER'S PRE-BID QUERIES

**TENDER LAYING OF UNDERGROUND PE PIPELINE NETWORK & ABOVEGROUND
INSTALLATIONS FOR PNG CONNECTIONS AT KOLHAPUR GA**

TENDER NO. -: HOGPL/WC/2022/02

**Pre-bid meeting held on : 03.06.2022
Date: 09.06.2022**



Sl. No.	Reference & Clause No.	Subject	Bidder's Query / Clarification	HOGPL / VCS Reply
COMMERCIAL				
1	Clause 8.4 of IFB Commercial Vol I of II Pg No. 9 of 101.	BEC Criteria	As per BEC requirement for sub contractor approved subcontractor required and letter of approval from client/end user required But sir we are working as a sub contractor under main contractor for IGL, Gail Gas & MNGL and I have approached for letter of approval for we are working as a sub contractor but all three companies/client/end user denied for approval letter so sir please consider the certificate given by main contractor to me.	Tender Condition shall Prevail.
2	Clause 10.0 of SCC Commercial Vol I of II Pg No. 59 of 101	PAYMENT TERMS AND MODE OF PAYMENT	Percentage of contract closer should be 5 % instead of 10%, as the duration of contract is 6 months only.	Tender Condition shall Prevail.
3	Clause 37.0 of SCC Commercial Vol I of II Pg No. 69 of 101.	CONTRACT PERFORMANCE BANK GUARANTEE	Percentage of CPBG (i.e. 10%) is quite higher for 6 months duration.	Tender Condition shall Prevail.
TECHNICAL				
1	Clause 5.0 Technical Volume II of II Pg No. 5 of 374	Scope of Work (OWNER's SCOPE OF SUPPLY)	Powder coated GI Pipes size from ½", ¾", 1", 1.5" & 12mm copper pipe and its associated fittings. It is not clear to us whether it is free or not.	Bidder to refer Clause No. 5 in Technical Volume II of II : Pg No. 5 of 374
2	Clause No. 12.4 of Technical Volume II of II Pg No. 37 of 374	STANDARD SPECIFICATION FOR LAYING OF POLYETHYLENE MAIN PIPELINES AND SERVICE PIPELINE FOR DOMESTIC CONNECTIONS	Hard rock is defined as trench material with a single piece of rock, dimension exceeding 1.0 m in any direction, which requires cutting only by use of chisel/pneumatic chisel/drill or sledge hammer or removal of the same by additional excavation technique approved by EIC. Additional rates shall be payable for hard rock excavation as per the item SOR no 7a over and above the pipeline laying rates. Excavation through soil mixed with small boulders that have been used for a road base will not be considered as hard rock for the purpose of payment.	Refer Corrigendum# 01



REPLY TO BIDDER'S PRE-BID QUERIES

**TENDER LAYING OF UNDERGROUND PE PIPELINE NETWORK & ABOVEGROUND
INSTALLATIONS FOR PNG CONNECTIONS AT KOLHAPUR GA**

TENDER NO. -: HOGPL/WC/2022/02

**Pre-bid meeting held on : 03.06.2022
Date: 09.06.2022**



Sl. No.	Reference & Clause No.	Subject	Bidder's Query / Clarification	HOGPL / VCS Reply
3	Schedule of Rates (SOR)	PL009.00 PNG CONNECTION IN PROJECT AREA PL009.01 Notes: 1. This SOR line item includes installation of Meters & Regulators for connectivity with GI/Cu pipe, appliance valves, isolation valves.	Which we understand that it is merely Installation of Meter, Regulator, Isolation valve, Appliance Valve and Carrying out NG conversion activity. Payment for Installation of GI/ CU Pipe will be paid separately as per SOR Item No: PL007. There is no fix Pipe (GI/CU) length like IGL or any other CGD. Same Interpretation will be there for PL010.00 PNG CONNECTION IN O&M AREA and PNG CONNECTIONS FOR COMMERCIAL CUSTOMERS. Sir, Most important whether we are having AVAILABILITY OF GAS OR NOT? If Yes then it is ok. But if Not then how much time it will take to have AVAILABILITY OF GAS.	Payment for Installation of GI/ CU Pipe will be paid as actual. Tender Condition Prevail.
4	Technical Volume	General	Please share the availability of gas in Kolhapur GA area	Kolhapur GA is Partially Gasified.